



15-171-30007-00-00

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
MAY 24 1965
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Casing Pulling has this

date requested permission to plug the following described well:
Saturn Oil & Gas Co.

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Saturn Oil & Gas Company,

Complete Address: Box #176, Cheyenne, Wyoming.

Lease Name: Smith Well No. 2-35

Location: CNE Sec. 35 Twp. 19 Rge. (E) (W) 33

County Scott Total Depth 2668 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

348'--8 5/8" surface pipe, cement circulated with 250 Sx.
2668'--4 1/2" Production casing cemented with 100 Sx. Top of
cement @ 2208'. Top perforations from 2526' to 2536'.

Spot 10 Sx. cement in 4 1/2" casing in and above top perforations.
Pull 4 1/2" to 600' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2"
to 330' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set
bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent