



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum, Company.

Complete Address: Box #2585, Amarillo, Texas.

Lease Name: Miller Well No. 1

Location: CSW-SW Sec. 28 Twp. 19 Rge. (E)(W) 33

County: Scott Total Depth 4850' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

367'--8 5/8" Surface casing, cement circulated with 270 Sx.
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 125 Sx.
dement thru DP. Pull DP to 400' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent