



15-171-20024-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company

Complete Address: Box #2585, Amarillo, Texas

Lease Name: Smith Well No. 11

Location: CNW-SW Sec. 26 Twp. 19 Rge. (E)(W) 33

County: Scott Total Depth 4700' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

402'--8 5/8" Surface casing, cement circulated with 270 Sx.  
Yucca elected to use cement for bottom of hole plugging, they to pick the zones to be cemented.

Circulate hole with heavy mud on bottom, Pull DP to 4650' and displace 25 Sx. cement thru DP. Pull DP to 4250' and displace and displace 55 Sx. cement thru DP. Pull DP to 950' and displace 55 Sx. cement thru DP. Pull DP to 402' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent