



15-171-20026-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
NOV 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Mucca Petroleum Company,

Complete Address: Box #2585, Amarillo, Texas.

Lease Name: Smith Well No. 13

Location: 150' W of CSE-N Sec. 26 Twp. 19 Rge. (E)(W) 33

County: Scott Total Depth 4710' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Delaney was instructed to plug the well as follows:

354'--8 5/8" Surface casing, cement circulated with 270 Sx.  
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 4600' and displace 30 Sx.  
cement thru DP. Pull DP to 1000' and displace 120 Sx. cement thru DP.  
Pull DP to 390' and displace 30 Sx. cement thru DP. Pull DP, set bridge  
@ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*K. L. Nichols*  
Conservation Division Agent