



15-171-20009-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company,

Complete Address: Box #2585, Amarillo, Texas.

Lease Name: Smith, Well No. 2

Location: CNW-NW Sec. 26 Twp. 19 Rge. (E)(W) 33

County: Scott. Total Depth 4868 Oil Well

Gas Well Input Well SDW Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

392'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.  
cement thru DP. Pull DP to 420' and displace 20 Sx. cement thru DP.  
Pull DP, set plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*N. L. Pichel*

Conservation Division Agent