



15-171-20035-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Smith of Rains & Williamson Oil Co., Inc has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc., & Petroleum Resources Co.,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Lehman Well No. E-1

Location: SW-SE-SE Sec. 30 Twp. 19 Rge. (E)(W)34

County: Scott Total Depth 5039' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Smith was instructed to plug the well as follows:

4 1/8" -- 8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 675'.

Circulate hole with heavy mud, Pull DP to 900' and displace 110 Cu. Ft. cement thru Dp. Pull DP to 435' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. J. Bihler
Conservation Division Agent