



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Thunder Bird and Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Minnix Well No. 1

Location: NW-SW Sec. 28 Twp. 19 Rge. (E)(W) 34

County: Acott Total Depth 5025' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

4 1/4' -- 8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 950' and displace 110 Cu. Ft. cement thru DP. Pull DP to 435' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. B. Fichale
Conservation Division Agent