

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-02059-00-00  
Spot: NENWSENW Sec/Twnshp/Rge: 13-21S-20E  
3892 feet from S Section Line, 3387 feet from E Section Line  
Lease Name: EWING B Well #: X-18X  
County: ANDERSON Total Vertical Depth: 660 feet

Operator License No.: 34170  
Op Name: SIRIUS ENERGY CORP.  
Address: 526 COUNTRY PL, SOUTH  
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	20		
PROD	2	625		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2011 12:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: RANDY TETER Company: \_\_\_\_\_ Phone: (785) 448-8571

Proposed Plugging Method: RUN 3/4" PIPE APPROX. 660' AND FILL 2" PIPE W/ APPROX. 20 SX. RUN 1" PIPE TO BOTTOM AND FILL BACKSIDE TO SURFACE W/ APPROX. 100 SX.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/08/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 3/4 INCH INSIDE 2 INCH CASING TO 625 FEET AND FILL WITH 12 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO 250 FEET AND PUMP 108 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF CEMENT.

Perfs:

RECEIVED

DEC 27 2011 LS

KCC Chanute Dist. #3

RECEIVED

JAN 03 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)