

1 090287

5-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,063-~~6000~~
SW NE, SEC. 1, T. 17 S, R. 28 W/EX

2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Schmieg Well # 1

Operator: Kaiser-Francis Oil Company

County Lane

Name & Address P.O. Box 21468

Well Total Depth 4670 151.77 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 21468, Tulsa, OK 74121-1468

Company to plug at: Hour: 10:45 a.m. Day: 25 Month: 5 Year: 1993

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Company (phone) 316-564-3214

were: 5 1/2" at 4357' w/150 sx cement, PBD 4298', Perfs at 4081-84, 4090-95, 4269-72'

1st plug set CIBP 100' above perfs,

2nd plug perforate at 1300' and pump 200 sx cement in 5 1/2",

3rd plug pump 200 sx cement in 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 25 Month: 5 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4030',

2nd plug perforated casing at 1300' and pumped in 200 sx cement,

3rd plug hooked onto backside and pumped in 200 sx cement.

Maximum pressure 400 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

DATE 6-8-93

Signed [Signature] (TECHNICIAN)

RECEIVED JUN 04 1993 6-4-93

INV. NO. 37849-5-25

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84