

1 050667

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,244-0000  
2790 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4151

Lease Name Crane Pet. Mansell Well # 1

Operator: Crane Petroleum Inc  
Name & Address: 5600 S. Syracuse Cir  
Ste 205-A  
Englewood CO 80110

County Lane 150.96  
Well Total Depth 4645 (Miss) feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 215'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address Pratt, P.O. Box 329 Pratt Kansas 67124

Company to plug at: Hour: 5:00pm Day: 11 Month: November Year: 19 85

Plugging proposal received from Tony Ernst

(company name) Wheatstate (phone) 316-672-7514

Work: Keep hole full of good mud & spot plugs through drill pipe. 1st plug @ 2160' w/50sx of cement, 2nd plug @ 1260' w/80sx of cement, 3rd plug 20' below base of surface w/40sx, 4th plug @ 40' with solid bridge plug + 10sx. Circulate Rathole w/15sx Circulate Mousehole w/15sx  
Plugging Proposal Received by: Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7:45pm Day: 11 Month: November Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of good mud & spotted plugs through drill pipe 1st plug @ 2160' w/50sx of cement, 2nd plug @ 1260 w/80sx of cement, 3rd plug @ 250' w/40sx of cement 4th plug @ 40' w/solid bridge plug + 10sx of cement Circulate rathole w/15sx Circulate Mousehole w/15sx

Remarks: B.J. Titan pumped 60/40 pozmix 6% gel cement  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE NOV 22 1985

NOV 14 1985  
11-14-85

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 11113

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84