

To: 1 090286
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-25 API NUMBER 15-101-20,144-0000

NE NW SE, SEC. 1, T. 17 S, R. 28 W/E
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Operator: Kaiser-Francis Oil Company
Name &
Address P.O. Box 21468
Tulsa, OK 74121-1468

Lease Name Schneider Well # 1

County Lane

Well Total Depth 4350 141.37 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 21468, Tulsa, OK 74121-1468

Company to plug at: Hour: 12:50 p.m. Day: 25 Month: 5 Year: 19 93

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Company (phone) 316-564-3214

were: 5 1/2" at 4349' w/150 sx cement, PBTD 4349', Perfs at 4082-86', 4092-96'-squeezed
1st plug set CIBP 100' above perforations,
2nd plug perforate at 1300' and pump 200 sx cement in 5 1/2",
3rd plug pump 200 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 25 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4030',
2nd plug perforated at 1300', pumped in 200 sx cement,
3rd plug hooked onto backside and pumped in 200 sx cement.
Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

(I (old, ~~xxxxxxx~~) observe this plugging.

DATE 6-8-93

INV. NO. 37848

Signed _____ (TECHNICIAN) JUN 4 1993

RECEIVED STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84

5-25