

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-133 - 01951 - 00 - 00
 NW SW SE Sec/Twp/Rge 4-28-18E
~~10512322~~ (GPS) 10512322 feet from south section line
~~23221051~~ (GPS) 23221051 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# Cox gps # COX OW1
 Operator License # 101 County Neosho
 Operator: State Of Kansas Fee Fund Well Total Depth 650 (est) feet
 Name & Taylor Lease Project Production Pipe: NA Size Feet NA
 Address _____ Surface Casing: NA Size Feet NA
 AB oil well XXXXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: _____ Hour: _____ Day: 27 Month: 5 2009

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part XXXXXX None _____
TECHNICIAN

Operations Completed: Hour: _____ Day: 27 Month: 5 2009

Actual Plugging Report: Surface pipe was installed to bring well to surface. The well was then drilled on thru rocks and wood to 300'. A 1" cement string was washed to 625' and the well pumped full of cement from btm to top thru this cement string. A total of 188 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
SEP 14 2009

KCC WICHITA

Remarks: Control #20090047-001
 (If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed: Alan M. Dunning
 TECHNICIAN