

10-31

6 061982

009-23,914.00.00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE, SEC. 27, T 16 S, R 12 W/E

2310 feet from S section line
1650 feet from E section line

Lease Name McLaughlin Well # 10
County Barton 111.15

Well Total Depth 3420 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 388

TECHNICIAN'S PLUGGING REPORT

Operator License # 5929

Operator: Duke Drilling Co.

Name & Address Box 823

Great Bend, Ks. 67530

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768 Great Bend, Ks. 67530

Company to plug at: Hour: 11:00 AM Day: 31 Month: Oct Year: 19 89

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Co. (phone) 316-793-8366

were: Order 225 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 12:15 PM Day: 31 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 388' w/175 sks. 5 1/2" set at 3419' w/125 sks. Top perf at 3385'. Plugged bottom w/sand and 5 sks cement to 3325'.

Shot pipe one time and recovered 2032'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 200 sks cement w/1000 psi.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1989

Remarks: By B. J. T. tan Ran line to 1000'.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 16 1989

INV. NO. 26466

10-31

Signed Gilbert G. Scheck
(TECHNICIAN)