

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-01304-00-00
Spot: SESESE Sec/Twnshp/Rge: 33-22S-15W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: FERGUS A Well #: 1
County: PAWNEE Total Vertical Depth: 4059 feet

Operator License No.: 33406
Op Name: GARNER, THOMAS
Address: 305 E 7TH
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3973		
SURF	9.625	657		WITH 415 SX CMT
PROD	7	4058	1082	WITH 85 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2011 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: THOMAS GARNER Company: THOMAS GARNER Phone: (620) 793-0766

Proposed Plugging Method: PUMP 75 SX CMT WITH 300# HULLS & DISPLACE TO 3400'. PLUG AT 990' WITH 20 SX GEL & 80 SX CMT. PLUG AT 690' WITH 80 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 12/19/2011 1:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP SET @ 3973'. PUMPED 75 SX CMT WITH 300# HULLS. DISPLACED TO 3400'. 1ST PLUG AT 993' WITH 20 SX GEL & 80 SX CMT. SDFW. 2ND PLUG AT 682' WITH 80 SX CMT. 3RD PLUG AT 341' WITH 50 SX CMT. 4TH PLUG AT 62' WITH 35 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4004	4014		SIMPSON
3726	3730		KANSAS CITY
3553	3559		KANSAS CITY

Remarks: USED60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
DEC 19 2011
KCC DODGE CITY

RECEIVED
JAN 06 2012
KCC WICHITA
1/18/12