

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22021-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 11-31S-35W
2015 feet from N Section Line, 2040 feet from E Section Line
Lease Name: YOUNG C Well #: 1
County: STEVENS Total Vertical Depth: 5798 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5400		WITH 2 SX CMT
CIBP		5520		WITH 2 SX CMT
SURF	8.625	1744		WITH 480 SX CMT
PROD	5.5	5766	1765	WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2011 9:30 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: WELL HAS CIBP @ 5520' WITH 2 SX CMT. FO TOOL @ 3269' WITH 60 SX CMT. SET CIBP @ 5400' WITH 2 SX CMT. SHOOT 5 1/2" CASING & POH. RIH W/TBG TO 1800' & PUMP 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/22/2011 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

FO TOOL @ 3269' WITH 60 SX CMT PER SCOUT CARD SET CIBP @ 5400' WITH 2 SX CMT. 1ST PLUG RIH W/ TBG TO 1845' & PUMPED 60 SX CMT. 2ND PLUG POH TO 600' & PUMPED 50 SX CMT. 3RD PLUG FILLED HOLE FROM 60' TO SURFACE WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5628	5640		CHESTER
5460	5470		MORROW

RECEIVED
JAN 10 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
JAN 05 2012
KCC DODGE CITY

Form CP 3/3
1/18/12