

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20485-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 22-21S-13W
2396 feet from N Section Line, 3011 feet from W Section Line
Lease Name: SCHULTZ Well #: 1
County: STAFFORD Total Vertical Depth: 3695 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	286		WITH 250 SX CMT
PROD	5.5	3694	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2011 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING Phone: (620) 792-7607

Proposed Plugging Method: PERFORATE 5 1/2" @ 760'. RUN TBG TO 3650' & PUMP 10 SX GEL & 40 SX CMT WITH 2 SX GEL MIXED IN. PULL TBG TO 760' & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2011 11:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFORATED 5 1/2" @ 760'. RAN TBG TO 3650' & PUMPED 10 SX GEL & 40 SX CMT WITH 2 SX HULLS MIXED IN. PULLED TBG TO 783'. PUMPED 120 SX CMT CIRCULATING CMT TO SURFACE. PULLED TBG OUT OF HOLE. PUMPED 140 SX CMT DOWN 5 1/2" CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3663	3681		ARBUCKLE
3508	3536		LKC

RECEIVED
JAN 10 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

JAN 05 2012

KCC DODGE CITY

Form CP-373

✓ 1/18/12