

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23350-00-00
Spot: NESWNE Sec/Twnshp/Rge: 2-8S-21W
1600 feet from N Section Line, 1710 feet from E Section Line
Lease Name: ATKISSON Well #: 1
County: GRAHAM Total Vertical Depth: 3654 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 SX
T1	1.5	3532		
PROD	5.5	3564		450 SX

Well Type: SWD UIC Docket No: D30099.0 Date/Time to Plug: 12/28/2011 9:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND Phone: (785) 625-5891

Proposed Plugging Method: Order 300 sx 60/40 pozmix w/4%gel, 11 sx gel, 300# hulls
Was dual completed well

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2011 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing. Pumped 75 sx cement w/300# hulls followed by 11 sx gel.
Pumped 225 sx cement.
Max Press.- 400# SIP- 100#
Visually checked annulus. Cement to surface.

Perfs:

Top	Bot	Thru	Comments
3492	3495		
3486	3488		LKC
3468	3472		LKC
3383	3386		LKC
3302	3305		LKC
3222	3226		LKC

RECEIVED
JAN 12 2012
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING TICKET #555

Plugged through: CSG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

JAN 10 2012

Form CP-2/3

cc to UIC 1/13/12
1/18/12