

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00191-00-00
Spot: SWSWNSW Sec/Twnshp/Rge: 12-23S-38W
1350 feet from S Section Line, 3941 feet from E Section Line
Lease Name: LOHMAN Well #: 1
County: KEARNY Total Vertical Depth: 2805 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2590		
SURF	8.625	949		WITH 400 SX CMT
PROD	5.5	2803	0	WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/27/2011 10:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ROD KAPP Company: BP AMERICA Phone: (281) 366-4395

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2011 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD 2715'. 1ST PLUG SET CIBP @ 2590' & 2 SX CMT. LOAD HOLE & TEST CASING TO 300# FOR 30 MINUTES. 2ND PLUG RAN BOND LOG FROM 2414' TO 650'. TOC @ 854'. PERFORATE CASING AT 820'. ESTABLISH CIRCULATION AT 2 BPM. 12/28/11: 3RD PLUG TIHWT TO 2580'. MIX & PUMP 145 SX CMT. ESTIMATE TOC @ 1000'. TOOHW. 4TH PLUG HOOK UP TO 5 1/2" CASING & CIRCULATE 5 1/2" X 8 5/8" ANNULUS FROM 820' TO SURFACE WITH 180 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2678	2698		
2624	2654		


RECEIVED
JAN 12 2012
KCC WICHITA

Remarks: USED CLASS C COMMON & 2% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JAN 06 2012
KCC DODGE CITY

Form CP-2/3

