

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21299-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 1-32S-31W
4845 feet from S Section Line, 2205 feet from E Section Line
Lease Name: SAUNDERS Well #: 1-1
County: SEWARD Total Vertical Depth: 6055 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1721		WITH 700 SX CMT
PROD	5.5	6054	1900	WITH 260 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/06/2012 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 5450' & 5 SX CMT OR SET CIBP @ 5450' WITH 2 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 01/06/2012 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND TO 5450' & 5 SX CMT ON TOP. 1ST PLUG AT 1740' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5500	5504		MORROW SAND

RECEIVED
JAN 12 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Steve Durrant

(TECHNICIAN)

RECEIVED
JAN 10 2012
KCC DODGE CITY

Form CP-2/3

1/18/12