

15-169-20097-00-00
State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

November 10, 1979

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Kevin Hough of Berentz Drilling Co. has this
date requested permission to plug the following described well:

Mr. Hough guarantees payment of the plugging fee.

Operator's full Name: Gene Petroleum Company

Complete Address: 300 Sutton Place, Wichita, Kansas 67202

Lease Name: Redden Well No. 1-B

Location: SE SE SE Sec. 36 Twp. 16 Rge. 2 (E) (W) X

County: Saline Total Depth 2780' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hough was instructed to plug the well as follows:

8 5/8" - 166' set @ 172' - cement circulated. Fill hole with mud
to 160'. Push plug and 1/2 sack hulls to 160' and
Cement hole with 25 sacks cement. Fill hole with mud
to 40'. Push plug and 1/2 sack hulls to 40' and
Cap hole with 13 sacks cement. Bridge rat hole and
Cement with 2 Sacks.

Very truly yours,

[Signature]
Conservation Division Agent

RECEIVED
NOV 13 1979
CONSERVATION DIVISION
Wichita, Kansas