



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

May 14, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Jerry Plouffe of Blackstone Drilling Inc. has this

date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Co., Inc.

Complete Address: 670 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Mayer Well No. 1

Location: NW NE SW Sec. 34 Twp. 16 Rge. 2 (E) (W) X

County Saline Total Depth 2902' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 130'. Set
rock bridge from 130' to 125' and cement with 20 sacks
through drill pipe. Fill hole with mud to 40'. Push
plug and $\frac{1}{4}$ sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Robert J. Loman
 Conservation Division Agent

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 20 1963
 05-20-1963
 CONSERVATION DIVISION
 Wichita, Kansas