

State of Kansas



15-169-19061-00-00
State Corporation Commission

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 26, 1965

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1965
06-03-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Walter J. Nelson
c/o Art Lamb
Complete Address: 2809 King, Hutchinson, Kansas

Lease Name: Holmquist Estate Well No. 1

Location: C NW SE Sec. 29 Twp. 15 Rgs. 3 (W)

County Saline Total Depth 3440' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3410' and cement with 3 sacks.
Fill hole with mud to 310'. Set rock bridge from 310' to
300' and cement hole with 25 sacks. Fill hole with mud to
40'. Set rock bridge from 40' to 30' and cap hole with 10
sacks cement.

Very truly yours,

Conservation Division Agent