



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

April 4, 1963

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

APR 9 1963
 04-09-1963
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Troy Smith of Kent Well Servicing Co., Inc. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Mutual Oil Company, Inc.

Complete Address: Planters State Bank Arcade, Salina, Kansas

Lease Name: Heddquist Well No. 1

Location: NE NE SE NW ~~NE NE SE~~ WSE Sec. 28 Twp. 15 Rge. 3 (E) (W) X

County Saline Total Depth 3375' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:
 (Packer set at 3200') Fill hole with sand to 3195' and
 cement with 5 sacks. Fill hole with mud to 210'. Set rock
 bridge from 210' to 200' and cement with 20 sacks. Fill
 Hole with mud to 40'. Set rock bridge from 40' to 30' and
 cap hole with 10 sacks cement.

Very truly yours,

L. J. Loman
 Conservation Division Agent