

State of Kansas



15-169-2008-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

June 19, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 30 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 06-30-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: H-30 Drilling, Inc.

Complete Address: 200 N. Main, Wichita, Kansas 67202

Lease Name: Miller Well No. 1

Location: NW SW Sec. 22 Twp. 15 Rge. 3 (E)(W) X

County: Saline Total Depth 3322' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 3 sacks cement.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent