

State of Kansas



15-169-00475-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
APR 25 1967
04-25-1967
CONSERVATION DIVISION
Wichita, Kansas

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 21, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Company

Complete Address: Drawer 712, El Dorado, Kansas 67042

Lease Name: R. J. Tinkler Well No. 1

Location: C NW NW Sec. 25 Twp. 15 Rge. 3 (X) (W) X

County Saline Total Depth 3250' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3200' and cement with 5 sacks.

Fill hole with mud to 245'. Set rock bridge from 245' to 235' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent