

State of Kansas



15-1169-20006-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

July 20, 1967

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 1 1967  
08-01-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Vandever Petroleum Company

Complete Address: Mayo Bldg., Tulsa, Oklahoma

Lease Name: Oscar Stroback Well No. 1

Location: C NE SE Sec. 22 Twp. 15 Rge. 3 (E)(W) X

County Saline Total Depth 3490' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 150'. Push plug and 1/4 sack hulls to 150' and  
cement hole with 20 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent