

15-169-19040-00-01

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 6 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 01-06-1969

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

January 2, 1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Art Small of same has this date requested permission to plug the following described well:

Mr. Small guarantees payment of the plugging fee.

Operator's full Name: Art Small

Complete Address: Route 3, Salina, Kansas

Lease Name: Percival Well No. 1

Location: NE NW SE Sec. 17 Twp. 15 Rge. 3 (W) X

County: Saline Total Depth 3431' Oil Well
 (OWWO)

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Small was instructed to plug the well as follows:

Fill hole with mud to 290'. Push plug and 1/4 sack hulls to 290' and
cement hole with 25 sacks cement through drill pipe. Fill hole with mud
to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

Conservation Division Agent