

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dorchester Exploration, Incorporated,

Complete Address 1204 Vaughn Building, Midland, Texas.

Lease Name Grimes Well No. 1

Location CSE Sec. 11 Twp. 20 Rge. (E) (W) 40

County Greeley Total Depth 2846'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sterling Drilling Company,

Address Box #129, Sterling, Kansas. License No.

Operation Completed: Hour 9:00 PM Day 13 Month 2 Year 1973

The above well was plugged as follows:

369'--10 3/4" Surface casing, cement circulated with 200 Sx. (9" Hole).
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 140 Cu. Ft. cement
thru DP from 1240' to 925'. Pulled DP to 400' and displaced 40 Cu. Ft. cement thru
DP from 400' to 325'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 20 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 2/22/73

INV. NO. 9008-W