

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-169- ¹⁹⁰³¹⁻⁰⁰⁻⁰⁰ SWD ✓

245 North Water
Wichita, KS 67202

Operator's Full Name L.B. Jackson Company

Complete Address 4609 E. 31st Street, Tulsa, Oklahoma 74135

Lease Name Craig Well No. 1

Location SW SW NW Sec. 28 Twp. 14 Rge. 2 (~~15~~) (West)

County Saline Total Depth 3339'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Nicholas Casing Pulling and Halliburton Co.

Address Box 373, Geneseo, Kansas License No. 711

Operation Completed: Hour: 6 PM Day: 19 Month: November Year: 1980

The above well was plugged as follows: 10 3/4" - 244' - ? 5 1/2" - 3804' - ?

Parted 1 Joint down while trying to remove slips. Hole squeezed
with 3 sacks hulls - 15 sacks gel-mud, and 100 sacks cement
pumped into 10 3/4" surface casing. Cement came up in cellar
and out in wheat field before holes in casing were shut off by
pumping rags and hulls ahead of cement.
recovered 1-32' Joint of 5 1/2"

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 12-15-80

INV. NO. 3783-w