

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

Authority July 13, 1981  
API Number 15-075-26,263

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Woolsey Petroleum Corporation

Complete Address 300 W. Douglas # 400, Wichita Kans

Lease Name Spencer Well No. 1

Location C. NE. NW. Sec. 2 Twp. 23 Rge. 39 (East) (West)

County Hamilton Total Depth 5700

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated never produced

Plugging Contractor Midwest Casing Pulling

Address Sublette, Kans License No. 766

Operation Completed: Hour: 4:00 PM Day: 27 Month: Aug Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
08-31-81

There was 815' of 8 1/8" surface casing c.c.  
5 1/2" casing set to 5700; Perforations were  
2903-2910; Perforations squeezed & plug  
set at 2800; 1st plug at 940-800 with  
50 lbs cement to cover Cheyenne zone. 2nd  
plug at 750. Pushed rubber plug to 750.  
2nd plug at 750 with 35 lbs cement. 3rd  
plug at 40-0 with 10 lbs cement  
Then was 1806' of 5 1/2" salvaged.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1981  
Signed: Shane Thomas  
Conservation Division Agent

DATE 9-25-81

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 7465 W