

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION

OCT 2 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dare Gas Inc.  
Complete Address Box 544, Liberal, Kansas 67901  
Lease Name Plunkett Well No. 1  
Location C SW NE Sec. 7 Twp. 22 Rge. 42 (W)  
County Hamilton Total Depth 2750'  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Sargents Casing Pulling  
Address Box 506, Liberal, Kansas License No. 511  
Operation Completed: Hour 1:00Pm Day 25 Month 9 Year 1973

The above well was plugged as follows:

8 5/8" to 160' circulated w/ cement. 4 1/2" to 2750' cemented.

Top perforations 2678' Plug bottom w/ 15 sacks cement.

Top of cement 2550' Mud 2650' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 200'

Spotted 35 sacks cement 200' to 100' Mud 100' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.. Company Pump

Pulled 2600' of 4 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10-2-73

INV. NO. 7967-W

Signed: Edward J. Eves

Well Plugging Supervisor