

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 26 1963  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg. Wichita, Kansas

Lease Name Blanche Smitherman Unit. Well No. 1

Location C SW NE Sec. 13 Twp. 22 Rge. 42 (E) (W)

County Hamilton Total Depth 2674'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Halliburton Cementing Company

Address: Elkhart, Kansas License No.     

Operation Completed: Hour 6 PM Day 19 Month 11 Year 63

The Above well was plugged as follows:

7"-244' Circulated w/cement. 4 1/2"-2640' Circulated w/cement. Perforations-2626' to 1650'

25 Sacs cement 2666' to 2340' Mud 2340' to 1700'

15 Sacs cement 1700' to 1520' Mud 1520' to 400'

35 Sacs cement 400' to surface. No pipe pulled. Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 11/27/63

INV. NO. 8182-w