

KANSAS

*Y*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 21 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Colorado Interstate Gas Company

Complete Address Box 1087, Colorado Springs, Colorado 80944

Lease Name Cornwell Well No. 1

Location C SW Sec. 12 Twp. 26 Rge. 43 (E) (W)

County Hamilton Total Depth 2861'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 6:00PM Day 18 Month 3 Year 1973

The above well was plugged as follows:

8 5/8" to 789' circulated w/ cement. 5 1/2" to 2830' cemented.

Top perforations 2757' Plug bottom w/ 25 sacks cement.

Top of cement 1280' Mud 1280' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug. Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 1000' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Lewis*  
Well Plugging Supervisor

INVOICED

DATE 3/21/73  
INV. NO. 17154-U