

15-169-00210-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 8 1962  
02-08-1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Saline

Location: SW/4- Sec. 25 Twp. 15 Rge. 3 KRM (W) \_\_\_\_\_

Name of Field: Mentor Total Depth: 3295'

I have this date completed supervision of plugging of:

Lease Name: Collins Well No. I

Operator's Full Name: Mutual Oil Co.

Complete Address: P.O. Box 502 Salina, Kansas.

Plugging Contractor Knight Casing Pulling Co.

Address: P.O. Box 304 Chase, Kansas. License No. 436

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4:PM Day 3 Month 2 Year 62

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3295' back to 3285' and ran 5 sax cement w/ dump bailer.

Shot off and pulled 4 I/2" casing. Filled hole w/ mud from 3250' back to 240' set a 10'

rock bridge an ran 20 sax cement. Filled hole w/ mud from 195' back to 40' set a bridge

and ran 8 sax cement back to zero. 8 5/8" surface pipe 4' below ground level.

Signed: Bernard W. J. Brown  
Conservation Division Agent

Reviewed: Harold H. H. H.  
Field Supervisor

Remarks:

INVOICED

DATE 2/8/62

INV. NO. 4521-2