

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-164 20,113-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Energy Production, Inc.

Complete Address 604 One Main Place, Wichita, Kansas 67202

Lease Name Peterson Well No. 1

Location C W/2 SW SE Sec. 17 Twp. 15 Rge. 3 (~~East~~) (West)

County Saline Total Depth 3440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Nicholas Casing Pulling and Allied Cementing Co.

Address Box 373, Geneseo, Kansas License No. 711

Operation Completed: Hour: 1:15 PM Day: 4 Month: April Year: 19 81

The above well was plugged as follows: 8-5/8"-297-circ. 5 1/2"-3433'-75 sacks
Hole filled with sand to 3400' and cemented with 5 sacks cement.
Hole squeezed with 3 sacks hulls, 20 sacks gel-mud, and 85 sacks 50-50
pozmix w/4% gel and 3% cal. chloride pumped into 8-5/8" surface casing.
2680' of 5 1/2" casing recovered.

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1981
04-08-1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 5-15-81

INV. NO. 5374-W