

15-169-00265-00-01

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED

STATE CORPORATION COMMISSION

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 28 1961
07-28-1961
CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Saline

Location: SE-SE-SW- Sec. 18 Twp. 15s Rge. 3 ~~(E)~~ (W) _____

Name of Field: Smolin Total Depth: 3450'

I have this date completed supervision of plugging of:

Lease Name: Nelson Well No. T

Operator's Full Name: Mr Tom Brown

Complete Address: Lindsborg Kansas.

Plugging Contractor Bert Self Csaing-Bulling Co.

Address: R.R. # 4, Hutchinson Kansas. License No. 48

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6:PM Day 17 Month 7 Year 61

The above well was plugged as follows:

Filled hole W/ sand from T.D. 3450' back to 3435' ran 3 sax cement W/ dump bailer.

Shot off and pulled 4-1/2" casing. Filled hole W/ mud from 3400' back to 240' set a 10'

rock bridge and 20 sax cement. Filled hole W/ mud from 130' back to 30' set bridge and

8 sax cement. 8-5/8" surface pipe 4' below ground level.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 8/9/61

INV. NO. 3522-W