

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-169-20,087-00-00 (of this well)

Operator's Full Name Brandt Oil Company
Complete Address 1103 Douglas Bldg, Wichita, Kansas
Lease Name Carlin Well No. 1
Location SW SE NE Sec. 8 Twp. 15 Rge. 3 (E) (W) X
County Saline Total Depth 3470'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated _____
Plugging Contractor Blackstone Drilling, Inc.
Address Box 1184, McPherson, Kansas License No. _____
Operation Completed: Hour 6 AM Day 23 Month August Year 1978

The above well was plugged as follows:

8 1/8" - 359' cement Circulated (Possible lost circulation zone)
Hole Filled with mud to 250'. Plug and 1/4 sack hulls
pushed to 250' and hole cemented with 25 sacks cement
through drill pipe. Hole Filled with mud to 40'. Plug
and 1/2 sack hulls pushed to 40' and hole cemented to
base of cellar with 10 sacks cement. Rathole bridged
and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-25-78
INV. NO. 7938-W

RECEIVED
STATE CORPORATION COMMISSION
Signed: [Signature]
Well Plugging Supervisor
AUG 25 1978
08-25-1978
CONSERVATION DIVISION
Wichita, Kansas