

15-169-00783-00-00

RECEIVED
STATE CORPORATION COMMISSION

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

MAY 21 1962
05-21-62
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Saline

Location: N/2 N/2 N/W Sec. 19 Twp. 14 Rge. 2 ~~(E)~~ (W)

Name of Field: Saline "E" Total Depth: 3228'

I have this date completed supervision of plugging of:

Lease Name: Faith Well No. 1

Operator's Full Name: Frank J. Black

Complete Address: 600 W. Washington McPherson, Kansas

Plugging Contractor R.D. Pipe Pulling Co.

Address: Box 569 Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 12:N Day 2 Month II Year 61

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3228' back to 3215' ran 5 sax cement w/ dump bailer.
Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 3180' back to 200'. set a 10'
rock bridge and ran 20 sax cement from 190' back to 130'. Filled hole w/ mud from 130'
back to 30' set a 5' rock bridge and ran 8 sax cement from 25' back to zero 3' below ground
level. 8/ 5/8" surface pipe 3' below ground level.

Signed: Reed M. Jones
Conservation Division Agent

INVOICED

DATE 5/18/62
INV. NO. 5005-W

Reviewed: _____
Field Supervisor

Remarks: