

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-169-00407-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB & T Building, Wichita, Kansas 67202

Lease Name Anderson Well No. 1

Location SW SW Sec. 9 Twp. 14 Rge. 2 (E) (W)

County Saline Total Depth 3168 1/2'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated 7

Plugging Contractor Southwest Casing Pulling Inc.

Address Great Bend, Kansas License No. 399

Operation Completed: Hour 5 PM Day 24 Month 6 Year 71

The above well was plugged as follows:

- 8 5/8"-215'-Circulated w/cement. 4 1/2"-3168'-Cemented. Sand hole to 3150'.
- 4 Sax. cement 3150' to 3100'. Mud 3100' to 230'. Bridge 230' to 220'.
- 25 Sax. cement 220' to 150'. Mud 150' to 40'. Bridge 40' to 30'.
- 10 Sax. cement 30' to 0. Pulled 2488'-4 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/30/71
INV. NO. 3922-W