

115-169-30026-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frank J. Black

Complete Address: Box 150 McPherson, Kansas 67460

Lease Name De-Bold Well No. # 1

Location C SE SE Sec. 5 Twp. 14 Rge. 2 (E) / (W)

County Saline Total Depth 3156'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co. Inc.

Address: Chase, Kansas License No. # 624

Operation Completed: Hour 11 AM Day 3 Month 9 Year 68

The Above well was plugged as follows:

13"-95'-Circulated w/cement. 8 5/8"-200'-Circulated w/cement. 4 1/2"-3153'-Cemented.

Sand hole to 3125'. 5 to 4 Sax. cement 3125' to 3075'. Mud 3075' to 220'.

Bridge 220' to 210'. 25 Sax. cement 210' to 135'. Mud 135' to 40'.

Bridge 40' to 30'. 10 Sax. cement 30' to 0'. Pulled 2614'-4 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: Hugh Scott
Well Plugging Supervisor

INVOICED

DATE 9/5/68
INV. NO. 8411-W