


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hamilton County, Sec. 30 Twp. 21S Rge. 40 (W)
Location as "NE/CNWxSWx" or footage from lines. C SW SW
Lease Owner Woolsey Petroleum Corporation
Lease Name Brehm Well No. 1
Office Address 300 W. Douglas, Suite 400, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 14 19 81
Application for plugging filed May 14 19 81
Application for plugging approved May 14 19 81
Plugging commenced May 14 19 81
Plugging completed May 14 19 81
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	806'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented @ 1250' With 35 Sacks Cement
Cemented @ 800' With 60 Sacks Cement
Cemented @ 40' With 10 Sacks Cement
Cemented Rat Hole With 5 Sacks Cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl F. Wakefield, Inc.
Address 300 West Douglas, Suite 500, Wichita, Ks. 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. William C. Wakefield,
President of Earl F. Wakefield, Inc. (employee or owner) or (owner or operator) of the above described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William C. Wakefield
300 W. Douglas, Suite 500, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of May, 19 81

My commission expires October 28, 1984 Carol J. Noel Notary Public.

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


API No. 15 — 075 — 20,379 0000
County Number

S. 30 T. 21 R. 40 ^{1/2} W

Loc. C SW SW

County Hamilton

640 Acres
N



Elev.: Gr. 3598'

DF KB 3606'

Operator
Woolsey Petroleum Corporation

Address
300 W. Douglas Suite 400 Wichita, KS 67202

Well No. 1-30 Lease Name Brehm

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Earl F. Wakefield, Inc. Geologist

Spud Date 5/9/81 Date Completed 5/14/81 Total Depth 2885' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24#	806'	HLC	300 RECF (1/2%) cc	

STATE CORPORATION COMMISSION
OCT 26 1981
CONSERVATION DIVISION
Wichita, Kansas

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Woolsey Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1-30	Lease Name Brehm	Dry Hole
S <u>30</u> T <u>21</u> R <u>40</u> ^W		
C SW SW		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Hollenburg	2730'	+ 876'		
Chase	2764'	+ 842'		
Winfield	2807'	+ 799'		
Towanda	2856'	+ 721'		
<p>DST #1 2784-2821' (Upper Winfield) 30-30-30-30 1st Op: VWB died 10" 2nd Op: NB Rec: 20'DM IHP 1480# FFP 40-54# IFP 27-40# FSIP 67# ISIP 188# FHP 1480# BHT 105°F</p>				
<p>DST #2 2785-2845' (Lower Winfield) 30-45-30-30 1st Op: VWB died 18" 2nd Op: NB Rec: 34'DM IHP 1561# FFP 81-94# IFP 54-81# FSIP 350# ISIP 417# FHP 1507# BHT 105°F</p>				
<p>DST #3 2840-2885' (Towanda) 30-30-32-53 1st Op: WB died 8" 2nd Op: NB Rec: 194'DM IHP 1453# FFP 81-108# IFP 14-81# FSIP 430# ISIP 457# FHP 1426# BHT 106°F</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p style="font-size: 1.2em; font-family: cursive;">Ronald J. Miller</p> <p style="text-align: center;">Signature</p> <p style="text-align: center;">Ronald J. Miller, Operations Manager</p> <p style="text-align: center;">Title</p> <p style="text-align: center;">June 15, 1981</p> <p style="text-align: center;">Date</p>
---------------	--