


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hamilton County, Sec. 2 Twp. 23 Rge. 39 E/A
Location as "NE/CNW}SW}" or footage from lines
C-NE-NW
Lease Owner Woolsey Petroleum Corp.
Lease Name Spencer Well No. 1
Office Address 300 W. Douglas, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Gas
Date Well completed 4-26-81 19
Application for plugging filed 6-29-81 19
Application for plugging approved 7-13-81 19
Plugging commenced 8-25-81 19
Plugging completed 8-27-81 19
Reason for abandonment of well or producing formation
Non Commercial Value
If a producing well is abandoned, date of last production
None 19



Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Thomas
Producing formation _____ Depth to top 2692' Bottom 2758' Total Depth of Well 5700'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	815'	0'
Production				5 1/2"	5200'	1806'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 2 sks. hulls & 25 sks. cement to 2450' pressured to 750 lbs.
Displaced to 950' 2/ mud
Pumped 50 sks. 940' to 800'
Layed down rest of 5 1/2' casing
Pushed plug to 750' & pumped 35 sks cement 750' to 650'
Put bridge & 10 sks. cement 40' to 0'
Cut off 8 5/8", 3' below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest casing Pulling Service
Permit # 766

STATE OF KANSAS COUNTY OF HASKELL, ss.
I, Edgar J. Eves (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Ks. 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of Sept., 1981

Sandra L Eves
Notary Public.

My commission expires 12-6-84



RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1982

CONSERVATION DIVISION
Wichita, Kansas

15-075-20363 0000

DRILLER'S LOG

WOOLSEY PETROLEUM CORPORATION
Spencer No. 1
C NE NW
Sec. 2-23S-39W
Hamilton Co., Ks.

Commenced: 1-17-81
Completed: 2-13-81

Surface Casing: 818' of 8-5/8"
cmtd w/300 sx Haliburton light,
2% cc, followed w/150 sx class
H, 3% cc.

FORMATION

DEPTH

Surface Hole	0 - 816
Sand	816 - 2265
Sand & Shale	2265 - 2557
Sand, Shale & Lime	2557 - 2730
Shale	2730 - 2780
Lime & Shale	2780 - 2885
Shale	2885 - 2954
Lime & Shale	2954 - 2990
Shale	2990 - 3020
Lime & Shale	3020 - 3565
Lime	3565 - 3820
Lime & Shale	3820 - 4085
Lime	4085 - 4295
Lime & Shale	4295 - 4645
Shale & Lime	4645 - 4790
Lime	4790 - 5060
Morrow	5060 - 5201
Lime	5201 - 5240
Mississippi	5240 - 5700 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

CHEYENNE DRILLING, INC.


Sharyn K. Shearmire

Sharyn K. Shearmire RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 4th day of March, 1981.

JUL - 1 1981
CONSERVATION DIVISION
Wichita, Kansas



Joyce Ann Hamill
Notary Public
Joyce Ann Hamill