


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hamilton County. Sec. 30 Twp. 21S Rge. 40
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
300' FNL & 100' FWL SE/4

Lease Owner Cities Service Company
Lease Name Hoyt A Well No. 1
Office Address 3545 N.W. 58th Street Oklahoma City, OK 73112
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole

Date Well completed 6-13-1979

Application for plugging filed 11-04-1980

Application for plugging approved 11-7-1980

Plugging commenced 1-02-1981

Plugging completed 1-06-1981

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation None Depth to top Bottom Total Depth of Well 2895'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None		Surface	400'	8-5/8"	400'	None
None		69'	2894'	4-1/2"	2825'	1987'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement spotted as follows:

1-05-81 Dowell pumped 20 sx From 2615' to Bottom

1-06-81 Dowell pumped 25 sx From 1900' to 1980'

Dowell pumped 35 sx From 350' to 450'

Capped with 10 sx From 4' to 40'

Cut 8-5/8" Casing 4' below surface and welded cap w/name & date

RECEIVED
CONSERVATION COMMISSION
FEB 17 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland & Johnson P.O. Box 94336, Oklahoma City, Oklahoma 73143

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
W. A. Givens (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.A. Givens W. A. Givens
3545 N.W. 58th Street Oklahoma City, OK 73112
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1981

Joyce S. Darter
Joyce S. Darter Notary Public.

My commission expires 6-10-84



51075 20166 3088
Tops

Exhibit
Schlumberger

SIMULTANEOUS
DUAL ENVELOPE

COMPANY *Cities Service Oil Company*

WELL *H. OYF A #1*

FIELD *BRA DSHAW*

COUNTY *HAMILTON* STATE *KANSAS*

COUNTY
FIELD
LOCATION
WELL
COMPANY

LOCATION
300' FWL & 100' FWL - SE 1/4
36 213 40N

FWL/CR
ONL/CR
BHE/CR

Permanent Datum: *Ground Level* Elev: *3588*
Log Measured From: *KB* 8 El. Above Perm. Datum
Drilling Measured From: *KB*

El. *3596*
OF *3595*
3588

Date: *11-9-76*
Run In: *ONE*
Depth Driller: *2195*
Depth Logger (Schl.): *2193*
Btm. Log Interval: *284*
Top Log Interval: *400*
Casing Driller: *875 @ 400*
Casing Logger: *400*
Bit Size: *7 1/8*
Type Fluid in Hole: *IMPERMEX*
Dens Visc: *10.1 31*
OH Fluid Loss: *40 11.8 ml*
Sample: *Circu*
R. Meas. Temp.: *083 @ 54° F*
R. Meas. Temp.: *053 @ 63° F*
R. Meas. Temp.: *M*
R. Meas. Temp.: *044 @ 101° F*
Circulation Stopped: *8:00/9*
Circulation Bottom: *10:00/9*
Circulation Top: *101*
Circulation Control: *1734 Liberal*
Circulation By: *REFSINGER*
Circulation By Mr: *P. Brody*

RECEIVED
STATE CORPORATION COMMISSION
NOV - 6 1980
CONSERVATION DIVISION
Wichita, Kansas