

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

HAMILTON County. Sec. 33 Twp. 21 Rge. 40 (X) (W)

Location as "NE/CNW/SW" or footage from lines C SW 1/4

Lease Owner KEITH L. RISING, TRUSTEE

Lease Name O. R. WHITENECK Well No. 1

Office Address BOX 811, LAMAR, COLORADO

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed NOVEMBER 18, 19 59

Application for plugging filed (BY PHONE) NOVEMBER 18, 19 59

Application for plugging approved (BY PHONE) NOVEMBER 18, 19 59

Plugging commenced NOVEMBER 18, 19 59

Plugging completed NOVEMBER 18, 19 59

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production - - - - - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. LEW BROCK

Producing formation UPPER WINFIELD Depth to top 2786 Bottom 2800 Total Depth of Well 2874 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
UPPER WINFIELD	SALT WATER	0	345	8 5/8"	10/23/59	LEFT IN HOLE
		0	2873	4 1/2"	10/30/59	11/18/59

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

A 4 1/2" HALLIBURTON PLUG WAS DRIVEN TO APPROXIMATELY 2295' AND CAPPED WITH 20 SACKS OF REGULAR CEMENT. PIPE WAS SHOT OFF AT 2004' AND PULLED.

A 8 5/8" HALLIBURTON PLUG WAS DRIVEN TO APPROXIMATELY 340' AFTER THE HOLE WAS FILLED WITH DRILLING MUD FROM THE PITS. THIS PLUG WAS CAPPED WITH 20 SACKS OF REGULAR CEMENT. HOLE WAS FILLED TO WITHIN 35' OF TOP WITH MUD FROM PITS AND AN 8 5/8" HALLIBURTON PLUG DRIVEN TO ABOUT 33'. THIS PLUG WAS CAPPED WITH 10 SACKS OF REGULAR CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1959
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. D. BURRIS

Address 509 EUGENE PLACE, GARDEN CITY, KANSAS

STATE OF COLORADO COUNTY OF PROWERS, ss.

KEITH L. RISING (X) (Name of owner) (X) (Name of operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Keith L. Rising

Box 811, LAMAR, COLORADO (Address)

SUBSCRIBED AND SWORN TO before me this 23 RD day of NOVEMBER, 19 59

Arthur C. Gordon Notary Public.

My commission expires March 11, 1962

