

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hamilton County. Sec. 6 Twp. 26 Rge. 42 ~~EX~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE SE NW


Lease Owner Ashland Exploration Inc.
Lease Name Hughes Cattle Co Well No. 1-6
Office Address Bbx 127, Satanta, Kansas 67870
Character of Well (Completed as Oil, Gas or Dry Hole)
Gas

Date Well completed 1977
Application for plugging filed 10-6-1978 1978
Application for plugging approved 10-8 1978
Plugging commenced 10-14 1978
Plugging completed 10-16 1978

Reason for abandonment of well or producing formation
Non Commercial Value
If a producing well is abandoned, date of last production
None 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Thomas
Producing formation Hugoton Depth to top 2232' Bottom 2354' Total Depth of Well 2850'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE				8 5/8"	680'	0'
Production				5 1/2"	2849'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump two sacks hulls & 15 sacks cement to 2100'-Pressured to 750#.

Displaced to 600'

Pumped 15 sacks cement 600' to 500'

Displaced to 40'

Put bridge & 5 sacks cement 40' to 0'

Cut off 8 5/8" & 5 1/2" 48" below ground level.

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling
Box F, Sublette, Kansas Kansas Permit #766

STATE OF KANSAS COUNTY OF Haskell, ss.
I Edgar J. Eves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Edgar J. Eves
Box F, Sublette, Kansas 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1978

Sandra L. Eves
Notary Public.

My commission expires 12-6-80

