


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
242 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Hamilton County, Sec. 24 Twp. 21 Rge. 42W (E) (W)  
Location as "NE/CNW/SW" or footage from lines 6 SE SE NESW NWB KCL  
Lease Owner Mayflo Oil Company  
Lease Name P. A. Craig Well No. 1-24  
Office Address 1220 Republic National Bank Building, Dallas 1, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed September 26, 1960 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced September 26, 1960 19  
Plugging completed September 26, 1960 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2910 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

13 3/8 circulated 350', 4 1/2, 2938', top perf. 2767',  
Sanded bottom of hole to 2450' with 10 sacks cement through  
tubing, pulled 800' 4 1/2" pipe, filled with mud to 340', bridged  
with 25 sacks cement, mud to 30', plug and filled to base of cellar  
with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H. & W. Well Service  
Address Perryton, Texas

STATE OF Illinois COUNTY OF Jackson, ss.  
W. Dean Hunt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Dean Hunt  
1435 Rep Nat'l Bk Bldg  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of June 1960  
My commission expires 6-1-67  
Dorothy L. Johnson  
Notary Public.



DOROTHY L. JOHNSON

P. A. CRAIG #1-2h

WELL RECORD:

LOCATION:

Section 2h, T21S-R12W  
Hamilton County, Kansas

Commenced: 6/15/60  
Completed: 6/22/60  
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling Co.  
Liberal Division  
Box 896  
Liberal, Kansas

CASING RECORD:

15 Jts. 13" 50# Surface Pipe  
cemented w/275 sx ED-5

P  
Y

	<u>LOG</u>	
Soil & Sand	0 -	40
Clay & Shale	40 -	310
Shale & Anhy	310 -	590
Shale, Lime & Pyrite	590 -	1240
Shale & Anhy	1240 -	1780
Shale & Lime	1780 -	2278
Shale & Anhy	2278 -	2863
Shale & Lime	2863 -	2940

2940' - Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY  
LIBERAL DIVISION

By F. R. Stubblefield

RECEIVED  
STATE CORPORATION COMMISSION

JUN 23 1966

LIBERAL DIVISION