

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21293-00-00
Spot: SESE Sec/Twnshp/Rge: 6-35S-30W
634 feet from S Section Line, 637 feet from E Section Line
Lease Name: ADAMS Well #: #1-6
County: MEADE Total Vertical Depth: 6198 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 9427 E. CROSS CREEK
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5700		WITH 4 SX CMT
SURF	8.625	1541		WITH 525 SX CMT
PROD	4.5	6190	1662	WITH 125 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/30/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID WITHROW Company: EDISON OPERATING Phone: (316) 613-1544

Proposed Plugging Method: SET CIBP @ 5700' WITH 2 SX CMT. SAND BACK PERFS WITH 5 SX CMT. SHOOT CASING. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL
Date/Time Plugging Completed: 01/02/2012 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5700' WITH 4 SX CMT. SAND BACK PERFS WITH 5 SX CMT. 1ST PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. NO CIRCULATION. 2ND PLUG AT 550' WITH 50 SX CMT. NO CIRCULATION. TAGGED CMT AT 1280'. 3RD PLUG RAN CASING TO 550' & SPOT 50 SX CMT. 4TH PLUG AT 40' WITH 30 SX CMT. RUN 1 JOINT INSIDE TOP OF CONDUCTOR. TAGGED CMT AT 28'. FILLED WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5770	5774		
5752	5758		


RECEIVED
JAN 12 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JAN 05 2012
KCC DODGE CITY

Form CP-23

1/18/12