

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23726-00-00  
Spot: W2SESWSW Sec/Twnshp/Rge: 26-21S-14W  
330 feet from S Section Line, 720 feet from W Section Line  
Lease Name: KELLER Well #: 26-2  
County: STAFFORD Total Vertical Depth: 3794 feet

Operator License No.: 32639  
Op Name: CORAL PRODUCTION CORPORATION  
Address: 1600 STOUT ST STE 1500  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	884		670 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2011 9:00 PM  
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC  
Proposal Rcvd. from: JEREMY STUCKY Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 3788' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 12/22/2011 11:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 3788' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED  
JAN 17 2012  
KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JAN 11 2012  
KCC DODGE CITY

Comp. 213  
1/18/12