

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01343-00-00
Spot: S2NESW Sec/Twnshp/Rge: 34-8S-16W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: DOANE Well #: 4
County: ROOKS Total Vertical Depth: 4290 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	225	0	200
PROD 7		3097	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2012 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: FRANCIS HITSCHMANN Company: CARMEN SCHMITT Phone: (620) 793-5100

Proposed
Plugging
Method:

D.V. TOOL AT 1746 W/ 130 SACKS OF CEMENT. Open Hole completion 3097'-3180'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2012 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3070' Copeland Acid & Cement pumped 75 sx common 3% cc w/200# hulls.
Pulled tubing to 2650' shut down for 1hr. Pumped 150sx 60/40 poz mix 4% gel w/200# hulls.
Pulled tubing to 1700' pumped 125 sx w/100# hulls, pulled tubing to 700' pumped 150 sx
cement circulated. P.T.O.H. Topped 7" casing off w/25 sx. Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3982	4290		ARBUCKLE

RECEIVED
JAN 18 2012

Remarks:

Plugged through: TBG

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

✓ 1/18/12

JAN 11 2012