

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19215-00-01
Spot: SWSENE Sec/Twnshp/Rge: 20-9S-16W
3007 feet from S Section Line, 1046 feet from E Section Line
Lease Name: DORR UNIT Well #: 706W
County: ROOKS Total Vertical Depth: 3455 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240		
T1	2.375	3063		
DVT		1301		
PKR		3063		
PROD	5.5	3454		175 sx

Well Type: EOR UIC Docket No: E09161.11 Date/Time to Plug: 12/22/2011 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CURTIS HITSCHMANN Company: Phone: (620) 793-2540

Proposed Plugging Method: DV tool @ 1301' to surface with 400 sx. Tubing parted in slips, ran overshot recovered 1118' of tubing, unable to recover below 1118'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2012 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1023', Copeland pumped 200 sx 60/40 poz mix 4% gel, followed w/ 200 sx cement w/ 250# hulls circulated cement. P.T.O.H. Topped 5 1/2" casing off w/ 50 sx cement, casing full.
01/06/2012 Topped off casing w/ 10 sx. Hooked up to backside and pumped 30 sx Max 200# SIP 200#

Perfs:

Top	Bot	Thru	Comments
3164	3377		

RECEIVED
JAN 10 2012
KCC WICHITA

Remarks: LEFT 1945' OF 2 3/8" CEMENT LINED TUBING AND PACKER IN HOLE.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN) CM

JAN 11 2012

Wato UIC 1/18/12 Form CP-2/3
1/18/12